

2024 SEATTLE CONSERVATION CORPS, DEPARTMENT OF PARKS & RECREATION

2024 ESTIMATING WORKSHEET

Project Name South Woods Trail Enhancement Sacha Wyatt 206 833 7960	Project Mgr/Customer+ Phone Number Nich Borer 206 849 6637	City of Shoreline Parks and Recreation 7/8/24
---	---	--

Resurface 700 Linear feet of Trail to 4inch depth and 4ft width with type 1 5/8's minus. Decommission 2 each social Trails totaling 218ft using onsite materials. Decommission trail split using arborist to build elevation to grade. Build 6 box steps at top of trail with Quarry spall outsoles. Build 2 box steps at lower trail entrance. Provide Corridor maintenance to achieve 4ft width of trail and preserve as much native plants as possible per forest steward request.

Labor	#Wrkrs	Days (8hrs)	Hrly Rate	Subtotal With OH 2.53	Cost
Project Manager			\$60.59	\$0.00	\$0.00
Sr. Supervisor			\$41.43	\$0.00	\$0.00
Supervisor	1	16	\$37.32	\$12,085.71	\$12,085.71
Crew Lead			\$23.90	\$0.00	\$0.00
Laborer	5	16	\$19.97	\$32,335.42	\$32,335.42
				\$0.00	\$0.00
Subtotal, Labor					\$44,421.13
Material & Equipment*	Quantity		Unit Cost	Subtotal	Cost
Bobcat (3 weeks)	1		\$2,800.00	\$2,800.00	\$2,800.00
Hilti Jack (3 weeks)	1		\$400.00	\$400.00	\$400.00
5/8s minus type #1	44.4	ton	\$50.00	\$2,220.00	\$2,220.00
Quarry Spall	1	ton	\$50.00	\$50.00	\$50.00
3/8 X 10" Hex Screws	2	1 box	\$25.00	\$50.00	\$50.00
Rebar	16	1each	\$13.00	\$208.00	\$208.00
6X8X12 lumber	8	1each	\$140.00	\$1,120.00	\$1,120.00
dump fees	0.5	ton	\$500.00	\$250.00	\$250.00
				\$0.00	\$0.00
				\$0.00	\$0.00
				\$0.00	\$0.00
				\$0.00	\$0.00
				\$0.00	\$0.00
				\$0.00	\$0.00
				\$0.00	\$0.00
				\$0.00	\$0.00
Subtotal, Material & Equipment					\$7,098.00
Disposal *	Type		Unit Cost	Subtotal	Cost
				\$0.00	\$0.00
				\$0.00	\$0.00
				\$0.00	\$0.00
				\$0.00	\$0.00
Subtotal Disposal					\$0.00
Subcontractor*	Work Description		Unit Cost	Subtotal	Cost
				0	\$0.00
				0	\$0.00
				0	\$0.00
Subtotal, Subcontractor *					\$0.00
TOTAL COST OF PROJECT					\$51,519.13

Any Cost Savings Applied will be returned to the client.